

# Appendix F

## Closure Plan

Omaha Public Power District  
Nebraska City Generating Station  
NC2 Ash Disposal Area

*January 2024*

*Revised March 2024*

*Revised February 2026*



## OPPD Nebraska City Station NC2 Ash Disposal Area Closure Plan

### Revision Log

This Closure Plan may be revised from time to time when procedures are changed. Because revisions to this document can be made on a periodic basis, document control is necessary. The most recent version of this Closure Plan is required to be posted on the CCR website. The revision log below will be updated every time the plan is amended.

Revision No.	Revision Date	Revised Sections	Originator	Notes
0	October 13, 2016	All Sections – Updated for Certification & Federal CCR Rule requirements	OPPD	Per CCR Rule – Separated State Closure & Post-Closure Plan
1	January 4, 2019	Section 2. Final Cover Design details	HDR	State Permit Renewal
2	January 19, 2024	Section 1.6 – Updated Site Life & Section 1.7 Updated Notifications to NDEE requirements	HDR	State Permit Renewal
3	March 2, 2024	Section 4.6 – Revised to address NDEE’s comment for independent PE certification.	HDR	State Permit Renewal
4	February 19, 2026	Section 1.2	OPPD	Updated Owner Contact Address

# Professional Engineer Certification

"I hereby certify that this Closure Plan for the NC2 Ash Disposal Area at the Omaha Public Power District Nebraska City Generating Station meets the requirements of the Coal Combustion Residual Rule 40 CFR 257.102(b). I am a duly licensed independent Professional Engineer under the laws of the State of Nebraska."

Print Name: Garrett Williams  
Signature:   
Date: 3/12/24  
License #: E-15124



My license renewal date is December 31<sup>st</sup>, 2024.

**Professional Engineer Certification Statement:**

I hereby certify that the amendments to this Closure Plan, dated February 2026, were prepared in accordance with the requirements of 40 CFR § 257.104 and have been developed in accordance with recognized and generally accepted good engineering practices.


**Name:** Megan B Seymar

**Title:** Professional Engineer

**License No.:** E-15931

**Signature:** Megan B Seymar

**Date:** 2-26-2026



My license renewal date is December 31, 2026 .



# Table of Contents

Professional Engineer Certification .....	ii
1 Site Identification .....	1
1.1 Introduction .....	1
1.2 Facility Identification .....	1
1.3 Legal Description .....	2
1.4 Maximum Inventory .....	2
1.5 Largest Area Requiring Final Cover .....	2
1.6 Site Life .....	3
1.7 Notifications .....	3
1.8 Schedule of Activities .....	3
1.9 Final Closure Certifications and Reports .....	4
1.10 Registration on Deed .....	4
2 Closure Plan .....	5
2.1 Final Cover System Design .....	5
2.2 Erosion Controls .....	9
2.3 Leachate Management System .....	9
2.4 Groundwater Monitoring System .....	9
2.5 Access Control .....	10
2.6 On-Site Structures and Roadways .....	10



# 1 Site Identification

## 1.1 Introduction

On April 17, 2015, the U.S. Environmental Protection Agency (EPA) published the final rule for the regulation and management of coal combustion residuals (CCR) under the Resource Conservation and Recovery Act (RCRA). The rule – effective on October 19, 2015 – applies to electric utilities and independent power producers that fall within NAICS code 221112, and the facility produces or stores CCR materials in impoundments or landfills. This regulation applies to Omaha Public Power District’s (OPPD’s) Nebraska City Generating Station.

OPPD has a two-unit (Unit 1 and Unit 2) fossil fuel-fired generating plant at the Nebraska City Generating Station (Station) southeast of Nebraska City, Nebraska. This Station has one existing active CCR landfill that is permitted under the current Nebraska Department of Environment and Energy (NDEE) Title 132 regulations for fossil fuel combustion ash disposal area (NC2 Ash Disposal Area). The NC2 Ash Disposal Area is a 40.7 Acre lined landfill, with available capacity for approximately 3,658,600 cubic yards of fossil fuel combustion ash. NC2 Ash Disposal Area continues to receive CCR for disposal. OPPD also has a closed CCR landfill (NC1 Landfill) that no longer receives ash and had a final closure approved by the NDEE on February 24, 2021.

This Closure Plan, prepared in accordance with NDEE Title 132, Chapter 4 and updated to comply with the Federal CCR Rule requirements, provides a description of the final cover system, closure activities, schedules, and features incorporated into the closure of the NC2 Ash Disposal Area. This Closure Plan must be amended whenever there is a change in the operation of the CCR landfill that would substantially affect the written closure plan or before or after closure activities have commenced, unanticipated events necessitate a revision of the written closure plan. OPPD will not implement modifications to the design or operations of the NC2 Ash Disposal Area that would result in modifications to this Closure Plan without prior approval from NDEE.

## 1.2 Facility Identification

Facility:	NC2 Ash Disposal Area
NDEE Permit No.:	NE0204421
Owner Contact Address:	Omaha Public Power District Sustainability & Environmental Affairs 1919 Aksarben Drive Omaha, Nebraska 68106
Facility Contact:	Manager Station Operations – (531) 226-2629



### 1.3 Legal Description

The Station is located 5.5 miles southeast of Nebraska City, along the west bank of the Missouri River. The Station property covers approximately 1,600 acres of river floodplain in portions of Sections 30 and 31, Township 8 North (T8N), Range 15 East (R15E), and Sections 25 and 36, T8N, R14E. The property map is provided in **Locational Criteria (Permit - Appendix K-1)**. The NC2 Ash Disposal Area is located in the S $\frac{1}{2}$ , SE $\frac{1}{4}$ , Section 25, T8N, R14E, in Otoe County, Nebraska, and the north 350 feet of the N $\frac{1}{2}$ , NE $\frac{1}{4}$ , of Section 36, T8N, R14E in Otoe County, Nebraska, containing approximately 40.7 acres for the total disposal area footprint.

### 1.4 Maximum Inventory

The Station was commissioned in 1979 with Unit 1. A second generating unit (Unit 2) was constructed and commissioned for commercial operation in May 2009. Fossil fuel combustion ash generated from both Units 1 and 2 have been placed in the NC2 Ash Disposal Area.

The NC2 Ash Disposal Area is approximately 40.7 acres, with available capacity for approximately 3,658,600 cubic yards of fossil fuel combustion ash. This excludes the liner and final cover. The total permitted capacity of the NC2 Ash Disposal Area was originally planned for 3,936,000 cubic yards, but decreased with the construction of Cell 2/3. During construction of Cell 2/3, the NDEE required revisions to the liner elevations resulting in a decrease of available capacity. As of the 2023 compiled topographic survey, remaining airspace is approximately 1,864,015 cubic yards for ash disposal.

For site life calculations, 100 percent of the fly ash and bottom ash produced from Unit 2 is assumed to be disposed in the NC2 Ash Disposal Area. Additionally, 60 percent of the fly ash and 95 percent of the bottom ash generated from Unit 1 are assumed to be disposed annually in the NC2 Ash Disposal Area.

Based on compaction of the disposed ash to 97 percent of maximum dry density, and the placement of ash from both Units 1 and 2, the NC2 Ash Disposal Area remaining life expectancy is projected to be approximately 5 years, from year 2024 to year 2029. Site life calculations and phasing are included in the **Phase Site Development Plan (Permit – Appendix B)**. The actual disposal area life is dependent upon Nebraska City Generating Station operations, amount of ash marketed for beneficial uses, and viability of bottom ash markets.

### 1.5 Largest Area Requiring Final Cover

The Cell 1 closure project in 2015 installed final cover over approximately 14.4 acres of NC2 Ash Disposal Area. As filling progresses in Cells 2/3, ash placement will overlap on the west side of Cell 1. Therefore, from the phase development on the **Permit Drawings (Permit – Appendix J)**, the largest area ever requiring final cover will be approximately 31 acres.



## 1.6 Site Life

The remaining life of the NC2 Ash Disposal Area was determined based on the design volume (available disposal capacity), actual and projected ash generated from the Units 1 and 2, 40% reuse of Unit 1 and no reuse of Unit 2 fly ash, 5% reuse of Unit 1 and no reuse of Unit 2 bottom ash, and an estimated average in-place density. The remaining disposal area is estimated to be approximately 5 years starting in 2024.

## 1.7 Notifications

The NC2 Ash Disposal Area will be used for the disposal of CCR only from OPPD's Nebraska City Generating Station. There will be no other users of the facility to be notified at the final closure.

OPPD will provide NDEE formal written notice of its intent to close the NC2 Ash Disposal Area at least 180 days prior to date of final receipt of CCR in accordance with NDEE Title 132 Chapter 4, Section 005.04. A copy of the notification will be placed in the facility's operating record. OPPD will provide NDEE notice of phased closure construction activities at least 30 days prior to start of construction, including the following:

- Projected date of the last receipt of waste (for final closure)
- Projected date of initiation of phased or final closure
- Proposed construction schedule
- Date of installation of final cover system

The NDEE also requires notification of the actual date of initiation of final closure and the actual date of completion of installation of the final cover system.

In accordance with the CCR rule requirements, the following closure-related notifications will be provided to the Director of NDEE:

- Notification that Closure Plan is available and posted to the CCR website, and any amendment thereof
- Notification of intent to close, including certification by an independent, qualified professional engineer for the design of the final cover system
- Notification of completion of closure, including certification by an independent, qualified professional engineer registered in the State of Nebraska.
- Notification that deed notation has been recorded

OPPD will place a copy of each notification summarized under this section or noted in NDEE Title 132 Chapter 4, Section 005 in the operating record.

## 1.8 Schedule of Activities

Within 30 days after the closure date, the closure plan shall be implemented. Closure activities will be completed in accordance with the closure plan within 6 months after closure date, depending on timing of the construction season or an extension has been received from NDEE.



OPPD will notify NDEE of the date of the initiation of final closure and the date of installation of the final cover system.

The **Post-Closure Plan (Permit – Appendix G)** will be implemented immediately after final closure is complete.

## **1.9 Final Closure Certifications and Reports**

OPPD will prepare, directly or through a contract, the documentation of closure in accordance with NDEE Title 132, Chapter 4. Documentation of closure will include certification by an independent professional engineer registered in the State of Nebraska verifying that closure has been completed in accordance with this or any subsequently updated Closure Plan. Documentation of closure will also include construction quality assurance documentation for each phased closure submitted to NDEE.

Certifications required by the Federal CCR Rule are included with the notifications described under **Section 1.7**.

When the NC2 Ash Disposal Area completes final closure, a survey and plat (prepared by a licensed surveyor in the State of Nebraska and meeting the minimum standards of property boundary surveys) will be submitted to NDEE. The survey plat will include the name of the property owner as it appears on the property deed, a legal description of the site, description of the CCR accepted, location of the CCR, approximate depth of fill, and location and description of groundwater management systems, which are to be maintained.

## **1.10 Registration on Deed**

Pursuant to NDEE, within 90 days following the NC2 Ash Disposal Area completion of installation of the final cover system for final closure, a notation will be recorded on the deed to the Station property or other instrument that is normally examined during a title search with the Otoe County Registrar of Deeds. A final plat will be filed with the Otoe County Registrar prepared by a registered land surveyor licensed in the State of Nebraska. OPPD will provide documentation of the deed notation to NDEE to show that such notation has been recorded, and a copy of this record and documentation will be placed in the operating record.

The notation on the deed will in perpetuity notify any potential purchaser of the property that:

- 1) A closed fossil fuel combustion ash disposal area exists on the property (the land has been used as a CCR landfill);
- 2) The type, depth, and location of CCR on the property is identified (as necessary) as well as the existence of any monitoring systems; and
- 3) Its use is restricted under the CCR rule post-closure care requirements of 40 CFR 257.104(d)(1)(iii) and may be restricted under NDEE Title 132, Chapter 4 to protect the monitoring system or any other components of the containment system.

## 2 Closure Plan

The purpose of this Closure Plan is to describe the steps necessary to close the NC2 Ash Disposal Area at any point during its active life and identify the final cover system, as required by the CCR rule to minimize the post-closure infiltration of liquids into the CCR, minimize the potential for adverse environmental impact, and minimize the need for further maintenance during the post-closure period. The closure of the NC2 Ash Disposal Area involves site preparation and grading, construction of the final cover system, and if not previously installed, construction of facilities for post-closure monitoring, maintenance, and care. The primary closure activities include adjusting site grades (both top and side slopes) if necessary, installing the final soil cover system with terraces and letdown structures, and installing vegetation. OPPD may close the remaining disposal area at one time or in phases after areas are filled to final grades and as funds are budgeted. **Permit Drawing Sheets C101 and C102 (Permit – Appendix J)** show the site development and final closure contours.

Installation of final cover for the NC2 Ash Disposal Area can begin when a phase reaches final elevation. Cell 1 (side slope closure to elevation 940) has had a 2-foot final soil cover installed in 2014/2015 in accordance with the NDEE Title 132 regulations. Current active cells will be closed in accordance with this updated Closure Plan and the requirements of the Federal CCR Rule. The discussion below applies to both phased closure and final closure. Closure activities at the NC2 Ash Disposal Area can include the following components:

- Final cover construction
- Storm water/drainage system
- Leachate management system
- Groundwater monitoring system
- Access controls
- On-site structures and roadways

The following description of activities is generally applicable to various closure alternatives (phased, premature, and final).

### 2.1 Final Cover System Design

The Federal CCR Rule requires the final cover system to meet either the requirements of 40 CFR 257.102(d)(3)(i) or the requirements of 40 CFR 257.102(d)(3)(ii). The proposed final cover design for the NC2 Ash Disposal Area meets the requirements of 40 CFR 257.102(d)(3)(ii) for alternative final cover systems and exceeds the current requirements of NDEE Title 132. Under this rule, the permeability of the final cover system must be less than or equal to the permeability of any bottom liner system or natural subsoils present, or a permeability no greater than  $1 \times 10^{-5}$  cm/sec, whichever is less. Additionally, the final cover system must include an erosion layer that provides protection from wind or water erosion that is equivalent to the erosion protection of a minimum of six inches of earthen material capable of sustaining native

plant growth. Finally, the disruption of the integrity of the final cover system must be minimized through a design that accommodates settling and subsidence.

### **2.1.1 Infiltration Layer**

40 CFR 257.102(d)(3)(ii)(A) requires the final cover system include an infiltration layer that has a permeability less than or equal to the permeability of any bottom liner system present. The bottom liner system of the NC2 Ash Disposal Area is composed of 2 feet of recompacted clay liner overlain by a 60 mil high-density polyethylene (HDPE) geomembrane and geotextile fabric layer. The permeability of this system is controlled by the permeability of the HDPE geomembrane. Therefore, the final cover system design proposed in this permit application includes an HDPE geomembrane. The final cover system design consists of 6 inches of structural fill overlain by a 60 mil HDPE geomembrane and geo-composite, followed by 18 inches of topsoil with vegetative cover (erosion layer).

The primary purpose of the infiltration layer is to prevent downward movement of moisture into the CCR. Soils for final cover infiltration layer will be obtained from either on or off-site borrow sources. Factors considered in soil selection include: percentage of fines; Plastic Index (based on Atterberg Limits-ASTM D4318); and percent gravel and stones. The infiltration layer construction will include successive horizontal lifts of suitable soils compacted to a minimum percent of Standard Proctor density to be determined with the source testing of soils. Horizontal lifts will not exceed six inches in compacted thickness. The final construction specification will reflect these considerations of soil properties, preparation, and compaction.

### **2.1.2 Erosion Layer**

The erosion layer of the proposed final cover design system is composed of 18 inches of topsoil. Soils for the final cover erosion layer will be obtained from one or more of the following sources:

- On-site stockpiles/borrow source
- Off-site borrow source
- NC2 clarifier sediment (or as soil amendment)

The erosion layer may be further amended with compost and/or fertilizer, when necessary. This erosion layer serves several purposes including: 1) to allow run-off of major storm events while inhibiting erosion; 2) to support vegetation which will not extend into the infiltration layer; 3) to reduce long-term maintenance by supporting diverse species of grasses, which reproduce voluntarily, and are low maintenance; and 4) to encourage evapotranspiration as a means of controlling liquid migration to the infiltration layer.

Factors to be considered in erosion layer soil selection include agricultural properties (e.g., pH, sodium absorption ratio, nutrient levels [nitrogen, potassium, and phosphate]). The final construction specification will reflect these considerations of soil agricultural properties, discing, treatment, and methods of installation of grasses.

The side slopes of the NC2 Ash Disposal Area will be graded to no steeper than 3 horizontal to 1 vertical (3:1). The top surface of the disposal area will be graded and maintained at a minimum 2 percent and maximum 10 percent slope. The slopes and grades are generally designed to provide sheet flow drainage of storm water.

### 2.1.3 Final Cover Erosion Control Features

The final cover includes slopes, grades, terraces, letdown structures, and diversion berms designed to promote surface water run-off (to minimize infiltration) and without creating excessive erosion.

- Terraces will be constructed of compacted soils during final closure as depicted in **Permit Drawing Sheet C507 (Permit – Appendix J)**. Terraces will be constructed approximately every 30 vertical feet to minimize erosion rills and soil loss. A typical series of terraces is shown on **Permit Drawing Sheets C102 and C301 (Permit – Appendix J)**. Terraces will typically discharge into letdown structures.
- Letdown structures will convey stormwater runoff collected from the terraces and diversion berm to the perimeter drainage channels. Each letdown structure will be constructed of materials which will prevent erosion due to anticipated velocities of runoff during a storm event. A typical letdown structure is depicted in **Permit Drawing Sheet C506 (Permit – Appendix J)**.
- Diversion berms will be constructed near the grade break transition from the shallow slope on top of the CCR landfill to the 3:1 side slope to terminate sheet flow and direct stormwater to the letdown structures. The diversion berm detail is depicted on **Permit Drawing Sheet C507 (Permit – Appendix J)**.

The combination of soil types and grasses (in addition to slopes, grades, terraces and berms) have been selected to control the rate of erosion such that maximum soil loss does not exceed the excessive erosion rate of 5 tons per acre per year as required by NDEE. Based on the final closure elevations, contours and structures shown in the **Permit Drawings (Permit – Appendix J)**, the Revised Universal Soil Loss Equation (RUSLE2) predicts first year soil loss for conservation planning under new vegetative growth conditions at 4.8 tons per acre for the NC2 Ash Disposal Area. Under established grass conditions, second year and beyond, the predicted soil loss for conservation planning is 0.74 tons per acre per year (see calculations in **Permit – Appendix M**). This is equivalent to a loss of cover thickness of approximately 0.026 inches in the first year and 0.004 inches per year over the remaining post-closure period, using a soil density of 100 pounds per cubic foot and soil loss for conservation planning. This equates to approximately 0.142 inches of total soil loss over a 30-year post-closure period (post-closure period of 30 years required by Federal CCR Rule). Final cover soil loss (RUSLE2) calculations are included in **Permit - Appendix M-10**.

### 2.1.4 Cover Vegetation

The erosion layer will be treated with appropriate soil supplements, if necessary, in preparation for the planting of perennial grasses. Appropriate vegetative cover will be established and maintained as soon as practical after final grading.



The seedbed for initial planting should be tilled with a disc to approximately 3 inches and the soil should be adjusted with a cultipacker before seeding to achieve a firm smooth seedbed or utilize a drill that will compact the soil correctly for prairie grasses.

Permanent seeding will be used to provide a long-term, low maintenance vegetative cover. Based on the change to final cover design, grassing is anticipated to include a mixture of species. Seed mixtures anticipated to be used in the future are included in **Table 1**. Final seed mixture and application rates will be confirmed, and if appropriate, modified for each specific phase of capping.

All permanent seed shall be certified seed that meets published US Department of Agriculture, Federal Seed Act standards and bears an official “Certified Seed” label. Legume seed should be inoculated with the inoculant appropriate for the species.

**Table 1: Capping System Vegetative Cover**

GRASSES	Pounds of Pure Live Seed (PLS) PER ACRE
Fescue, Fawn	25
Ryegrass (Perennial)	15
Sideoats Grama (Butte or Trailway)	5
Switchgrass (Neb. 28, Blackwell, Pathfinder, or Cave-in-Rock)	3
Birdfoot Trefoil (Empire)	5

The final construction specifications will require the contractor to sample and analyze the soils used for final cover erosion layer to obtain recommendations on the type and amount of nutrients to add to the cover soil and for the seed application rates. Fertilizer and other soil amendments will be applied at the rate defined by the test recommendations. Fertilizer and other soil amendments shall be incorporated into the top 4 to 6 inches for permanent closure. Mulch products may include Hydro-mulch, peat moss, hay, or straw. Other materials may also be considered. Hydro-mulch shall be applied in accordance with manufacturer’s recommendations. Where hay or straw are utilized they shall be applied at a minimum rate of 4,000 pounds per acre. Hay and straw mulching shall be placed loose and immediately following spreading it will be anchored using a rolling coultter, wheatland packer or similar mulch crimper having wheels with V-shaped edges to force the mulch into the soil surface. Other methods of installation or anchoring may be considered if they can assure that the mulch is applied and anchored in a manner as to remain in place.

### **2.1.5 Construction Quality Assurance**

Construction of the final cover shall be in accordance with requirements of the **Construction Quality Assurance (CQA) Plan (Permit – Appendix I)**. OPPD will submit CQA documentation including a topographical survey showing final contours and a certification signed by an independent professional engineer registered in the State of Nebraska verifying that closure was completed in accordance with the approved closure plan and in accordance with the CQA Plan.

## **2.2 Erosion Controls**

Permanent erosion control features are described under the final cover system design (**Section 2.1**). Run-off will be returned to natural drainage.

For disturbances of more than 1 acre, silt fences or other erosion control measures will be installed, as necessary. Temporary erosion controls will consist of silt fence, filter socks, staked hay bales or other erosion control measures. These will only be utilized during construction of the final cover system on the landfill area or where stormwater is likely to discharge from the disposal area.

### **2.2.1 Storm Water/Drainage System**

Drainage structures such as ditches, culverts, and discharge structures have been constructed prior to closure. The final closure includes slopes, grades, terraces, and letdown structures designed to promote surface water run-off (to minimize infiltration) and without creating excessive erosion. Permanent drainage structures and ditches are designed to accommodate a 25-year, 24-hour storm event, as identified in the site drainage calculations (**Permit – Appendices M-11 through M-18**) and the **Run-on and Run-off System Control Plan (Appendix D)**.

## **2.3 Leachate Management System**

All leachate management facilities will be in place at the time of final closure, and no additional facilities will be required. The compacted ash and overall capping system will reduce leachate production as determined by HELP model runs (**Permit - Appendix M-5**).

## **2.4 Groundwater Monitoring System**

All installed monitoring wells at the time of final closure are anticipated to remain in use for the groundwater level measurements, detection monitoring program, and/or assessment monitoring. The wells are protected with bollards or other protection features from potential vehicular damage. The groundwater monitoring system is described in the **Groundwater Sampling and Analysis Plan (Permit – Appendix E)**.

## **2.5 Access Control**

The Station facilities are surrounded by a combination of barbed wire fence and chain link fence, with a security gate at the entrance. Access onto the Station site is through the gate, either with security personnel during administrative office hours or key card after hours. The power plant is staffed at all times. Unauthorized personnel will not be allowed on-site.

## **2.6 On-Site Structures and Roadways**

Ash silos and other structures may remain at the final closure of the NC2 Ash Disposal Area for future ash operations at an alternative disposal area. Maintenance equipment required during the post-closure period may remain on-site. Plant facility buildings will continue to function for ongoing Station operations.

The final disposal area site configuration will incorporate the roadways to access the groundwater monitoring wells, surface water facilities, and other appropriate areas.